

Bell Hole & Line Preparation

Prior to coming onsite with the pipe spool, all lines must be cleaned. Lines must be free of wax and debris and all fittings in the line must be dug up and taken out. Long radius bends in the line can't be sharper than the minimum bend radius of the pipe being installed. (Check with the pipe manufacturer to determine the minimum bend radius).

